BRUHAT BENGALURU MAHANAGARA PALIKE

YELAHANKA ZONE

NAME OF WORK* : *Improvements to Roads and Drains at lake view layout main road in kempegowda ward no -01.

								Estimate Cost Rs.	20.00	Lakhs
Sl. No	Description of Item	Unit	No.	L	B	D	Qty.	Rate	Amount
1	KSRB 2-2.1 : Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. specification. No. KBS 2.1(a) / 2.3.5 SR 2018-19								
		Cum							
	New Drains								
			2	130.00	1.05	0.95	259.35		
	Culvert		1	6.00	1.65	1.20	11.88		
							271.23	**316.94**	**85964.00**
	Basic Rate Rs	299.00							
	Add Area Weightage @ 6%	17.94							
	Total	**316.94**							
2	KSRB4.1.3: Providing and laying position plain cement concrete of Mix 1:4:8 with OPC cement @180Kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85 cum and fine aggregtes @ 0.57 cum machine mixed , concrete laid in layers not exeecding 15 cms, thick, well compacted , in foundation , including cost of all materials, Labour , HOM of Machinery, Curing complete as per Specifications. Specifications No. KBS 4.1, 4.2 (P12/4.3). SR 2018-19								
			2	130.00	0.90	0.15	35.10		
	Culvert		1	6.00	1.50	0.15	1.35		
							36.45	5408.12	**197126.00**
	Basic Rate	5102.00							
	Area Weightage @ 6%	306.12							
	Total	**5408.12**							
3	Providing and laying Plain /reinforced cement concrete for side drains wall and bottom thickness 15cm using M20 nominal mix concrete with OPC cement at 300kg with 20mm and down size granite metal coarse aggregate at 0.69 cum and fine aggregate at 0.43 cum machine mixed well compacted for walls at bottom including centring shuttering cost of materials HOM of machineries curing etc.completeexcluding cost of steel as per MORTH specification No.1500,1700,2200 Page No 271 Ite mo 37.59.2 SR 2018-19 (wall and bottom thickness 15cm.								
		Cum							
	Bottom raft								
			2	130.00	0.90	0.125	29.25		
	Culvert		1	6.00	1.50	0.15	1.35		
	Side wall								
	New Drains								
			4	130.00	0.15	0.75	58.50		
	Culvert		2	6.00	0.25	0.80	2.40		
						Total	**91.50**	7070.20	**646923.00**
	Basic Rate	6670.00							
	Add Area Weightage @ 6%	400.20							
	Total	**7070.20**							

Sl No.	Description of Item	Unit	No.	L	B	D	Qty.	Rate	Amount
4	KSRB 4.9.2:providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications. Specification No. TMT bars Fe 500 KBS 4.6.3 Page No. 18/ Item No. 4.46/ PWD SR 2018-19								
		Tonne							
	for Drain 50kg/cum		1	87.75	50.00		4387.50		
	for culvert 60kg/cum		1	3.75	60.00		225.00		
	Total						**4612.50**		
							4.61	75223.96	**346971.00**
	Basic Rate	70966.00							
	Add Area Weightage @ 6%	4257.96							
	Total	**75223.96**							
5	Supplying and fixing **precast** rainforced concrete slab 10cm thick including cost of reinforcement as per design and drawing material cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface stc., complete with all leads and lift conveyance charges, labour charges inclusive of cost of all materials.(Drain covering slab)								
		Sqm							
			2	127.00	0.75		190.50		
						Total	**190.50**	2337.00	**445199.00**
	Data rate	2337.00							
6	Providing precast slab of 250 mm thick including cost of all materials, labour, curing,transportation,loading ,unloading,etc.,complete as per the direction of engineer in charge-								
		Sqm							
			1	6.00	1.20		7.20		
							7.20	5418.00	**39010.00**
	Data rate	5418.00							
7	KSRRB M100-1 Loading and Unloading of Stone Boulder / Stone aggregate /sand/kaner/ Moorum KSRRB M100-1 Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications MORTH -100/ Chapter 1 (Page No.133/ Item No 17.1) SR 2018-19								
		Cum							
			Qty Vide Item No.1				**271.23**	87.56	**23748.00**
	Basic Rate for loading and unloading	57.00							
	Basic Rate for Haulage upto 8.00 k.m =1.28 X 2.50 X 8	25.60							
	Basic Rate	82.60							
	Area Weightage 6%	4.96							
	Grand Total	87.56							

Sl No	Description of Item	Unit	No.	L	B	D	Qty.	Rate	Amount
8	GST of 12% as per Govt Letter No PWD 65 RDF 2017 Dated 11-10-2018						Sub total		1784941.00
									214192.92
9	Miscellaneous and unforeseen charges	Ls							
									866.08
							Total Ammount Rs.		2000000.00
	(Rupees Twenty lskhs only)								

CERTIFICATE

1) The site has been inspected and the work is found to be necessary.
2 The rates adopted are as per PW,P IWTD SR of 2018-19
3) The provisions were made in this estimate are necessary and adequate.
4) The area comes under the Bruhat Bengaluru Mahanagara Palike Limits.
5) This work is not repeated in any other programs or Grants

Assistant Engineer
Ward No.1

Executive Engineer
Yelahanka-Division
B.B.M.P

Assistant Executive Engineer
Yelahanka Sub-Division
B.B.M.P

Administrative Approval

Accorded For Rs.20:00lakhs only
Head of A/C P1771
CER NO : 194 Dt: 25.02.19

TA

CE (YNK)

TECHNICALLY SANCTIONED FOR Rs. 20.00 L
Rupees Twenty Lakhs only
Under P.1771-2018 19
Registered as CE ( ) No. 9 9
Subject to conditions contained in enclosed memo EE ( ) No. /9/
Dt. Estimate A/ Sanctioned
EE/TS/36/18-19 No.
Dated 25.02.19 Rs. 20.00 Lacs

Executive Engineer

150 - YELAHANKA AC

BRUHAT BANGALORE MAHANAGAR PALIKE
WARD: 1- KEMPEGOWDA WARD

N

VILLAGE BOUNDARY
VILLAGE BOUNDARY
EXI. CMC WARD BND.
EXI. CMC WARD BND.
GOVINDAPURA
YELAHANKA AIRPORT AREA
BSF STC YELAHANKA
BELLARY ROAD
KEB LAYOUT PHASE-I
VILLAGE BOUNDARY
EXI CMC WARD BND
RYAN INTERNATIONAL SCHOOL
POLICE TRAINING CENTRE
SAI SPRING FIELD COLONY
ALI ESTATE
VASUDEVAPURA
BSF BUS STOP
VINAYAKNAGAR
G L RAJU COLONY
CANADIAN INTERNATIONAL SCHOOL
KEMCHENAHALLI
RAILWAY LINE
MACHENAHALLI
LAKE VIEW RESIDENCY
SATYAPPA ANJINAPPA KEMPAMMA LAYOUT
YALAHANKA KERE
BANGALORE SPOKES INDIA PVT LTD
VENKATALA
VENKATALA LAYOUT
VENKATAPPA LAYOUT
EXI CMC WARD BND
EXI CMC WARD BND
CHOWDESWARI LAYOUT
BELLARY ROAD
MARUTHI NAGAR
MARUTHINAGAR
KENDRIYA VIHAR
RAILWAY STATION
KAMAKSHAMMA LAYOUT
EXI CMC WARD BND
GHANIKARENA LAYOUT
BAZZAR ROAD
FM GOETZE PLANT
KULAPPA LAYOUT
BADRAPPA LAYOUT
YELAHANKA
MAHESHWARENAGAR
EAST COLONY
HOSPITAL ROAD
GANDHI NAGAR
N.E.S. MAIN RD
NEHRU NAGAR
DODDABALLAPURA RD
BELLARY ROAD
BELLARY ROAD BYPASS
JAKKUR ROAD
SURABHI LAYOUT
BELLARY ROAD
RAILWAY LINE
JAKKUR ROAD
EXI CMC WARD BND
VIDYASHILP ACADAMY SCHOOL
EXI CMC WARD BND
EXI CMC WARD BND
MANTRI
SHOBHA ULTIMA VILAS
DAS TEACHER LAYOUT

NOTIFICATION NO UDD 59 MLR 2009 DATE 15.07.10

INDEX

- PROPOSED WARD BOUNDARY
- RIVER/ DRAIN
- RAILWAY LINE
- ROAD